BRUHAT BANGALORE MAHANAGARA PALIKE

BYATARAYANAPURA ZONE

Name of Work : Pot hole filling to Roads in Ward No.05 (Jakkur) Byatarayanapura Sub Division.

					Estimate Cost			3000000.00	
Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB- M 3000-2: Making up loss of of Material/irregulatities on shoulder ot the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per s[ecifications. MORTH Specification No. 3003 (Page No. 265/ Item No.35.2, PWD SR 2018-19						Sqm		
	Srirampura Main Road Up to Railway Gate		1	3.00	2.00		6.00		
			1	5.00	1.80		9.00		
			1	5.00	2.80		14.00		
			1	6.00	2.50		15.00		
			1	5.00	1.00		5.00		
			1	1.00	2.15		2.15		
			1	6.00	1.20		7.20		
			1	5.00	3.00		15.00		
			1	5.00	5.00		25.00		
			1	6.00	1.00		6.00		
			1	2.00	1.20		2.40		
			1	1.00	1.00		1.00		
	Royal Enclave		1	6.00	2.00		12.00		
			1	2.00	2.00		4.00		
			1	1.00	1.75		1.75		
			1	5.00	2.00		10.00		
			1	2.00	8.00		16.00		
	12th A Cross		1	3.20	1.75		5.60		
			1	1.00	1.75		1.75		
	Jakkur 1st Cross and 2nd Cross		1	1.00	1.50		1.50		
			1	5.00	2.20		11.00		
			1	5.00	0.60		3.00		
			1	2.00	7.00		14.00		
			1	1.00	1.00		1.00		
	Govt School Road		1	2.00	2.00		4.00		
			1	4.50	1.00		4.50		
			1	2.00	1.90		3.80		
			1	2.00	1.90		3.80		
			1	1.00	1.00		1.00		
			1	3.00	1.00		3.00		
			1	2.00	1.00		2.00		
			1	5.00	0.09		0.45		
	Telelcom layout 15th Cross		1	6.00	4.00		24.00		
			1	1.00	1.00		1.00		
			1	5.00	3.00		15.00		
			1	3.00	4.50		13.50		
			1	4.00	4.80		19.20		
			1	8.00	9.00		72.00		
	2nd Main Road		1	3.00	5.20		15.60		
			1	4.60	2.30		10.58		
			1	2.00	1.00		2.00		
			1	4.00	5.00		20.00		
			1	8.00	4.00		32.00		

			1	1.00	1.00		1.00			
	7th Cross		1	1.00	1.00		1.00			
			1	2.00	1.60		3.20			
			1	1.00	0.80		0.80			
			1	2.00	1.00		2.00			
			1	2.00	2.00		4.00			
			1	3.00	2.00		6.00			
			1	3.50	3.00		10.50			
			1	1.00	4.00		4.00			
	11th Cross		1	1.80	2.00		3.60			
			1	1.00	1.00		1.00			
			1	3.00	2.00		6.00			
			1	3.00	0.00		0.00			
			1	1.00	1.00		1.00			
	Sampigehalli to Agrahara Layout		1	2.00	2.00		4.00			
			1	3.50	2.00		7.00			
			1	2.00	1.00		2.00			
			1	1.80	2.00		3.60			
			1	1.00	3.00		3.00			
			1	1.20	2.00		2.40			
			1	1.00	2.00		2.00			
			1	1.20	3.00		3.60			
			1	1.30	2.00		2.60			
			1	3.10	1.00		3.10			
			1	2.00	5.00		10.00			
							3684.64	29.68	109360.00	
	Basic Rate	28.00								
	Area Weightage @ 6%	1.68								
	Total	29.68								
2	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 170/ Item No. 20.18/ PWD SR 2018-19						Cum			
	Srirampura Main Road Up to Railway Gate		1	3.00	2.00	0.15	0.90			
			1	5.00	1.80	0.15	1.35			
			1	5.00	2.80	0.15	2.10			
			1	6.00	2.50	0.15	2.25			
			1	5.00	1.00	0.15	0.75			
			1	1.00	2.15	0.15	0.32			
			1	6.00	1.20	0.15	1.08			
			1	5.00	3.00	0.15	2.25			
			1	5.00	5.00	0.15	3.75			
			1	6.00	1.00	0.15	0.90			
			1	2.00	1.20	0.15	0.36			
			1	1.00	1.00	0.15	0.15			
	Royal Enclave		1	6.00	2.00	0.15	1.80			
			1	2.00	2.00	0.15	0.60			
			1	1.00	1.75	0.15	0.26			
			1	5.00	2.00	0.15	1.50			
			1	2.00	8.00	0.15	2.40			
	12th A Cross		1	3.20	1.75	0.15	0.84			
			1	1.00	1.75	0.15	0.26			

Jakkur 1st Cross and 2nd Cross		1	1.00	1.50	0.15	0.23		
		1	5.00	2.20	0.15	1.65		
		1	5.00	0.60	0.15	0.45		
		1	2.00	7.00	0.15	2.10		
		1	1.00	1.00	0.15	0.15		
Govt School Road		1	2.00	2.00	0.15	0.60		
		1	4.50	1.00	0.15	0.68		
		1	2.00	1.90	0.15	0.57		
		1	2.00	1.90	0.15	0.57		
		1	1.00	1.00	0.15	0.15		
		1	3.00	1.00	0.15	0.45		
		1	2.00	1.00	0.15	0.30		
		1	5.00	0.09	0.15	0.07		
Telelcom layout 15th Cross		1	6.00	4.00	0.15	3.60		
		1	1.00	1.00	0.15	0.15		
		1	5.00	3.00	0.15	2.25		
		1	3.00	4.50	0.15	2.03		
		1	4.00	4.80	0.15	2.88		
		1	8.00	9.00	0.15	10.80		
2nd Main Road		1	3.00	5.20	0.15	2.34		
		1	4.60	2.30	0.15	1.59		
		1	2.00	1.00	0.15	0.30		
		1	4.00	5.00	0.15	3.00		
		1	8.00	4.00	0.15	4.80		
		1	8.00	2.00	0.15	2.40		
		1	10.00	2.00	0.15	3.00		
14th Cross		1	4.00	5.00	0.15	3.00		
		1	2.00	2.00	0.15	0.60		
		1	10.00	1.00	0.15	1.50		
		1	2.00	2.00	0.15	0.60		
		1	5.20	3.00	0.15	2.34		
		1	3.00	2.00	0.15	0.90		
		1	8.00	1.10	0.15	1.32		
		1	5.00	0.90	0.15	0.68		
		1	2.00	6.00	0.15	1.80		
13th Cross		1	6.50	0.90	0.15	0.88		
		1	7.50	0.80	0.15	0.90		
		1	3.00	2.00	0.15	0.90		
		1	1.00	1.00	0.15	0.15		
		1	4.00	2.00	0.15	1.20		
		1	4.00	2.00	0.15	1.20		
		1	2.00	8.00	0.15	2.40		
		1	5.00	1.00	0.15	0.75		
		1	7.00	9.00	0.15	9.45		
12th Cross		1	3.00	0.80	0.15	0.36		
		1	2.00	0.80	0.15	0.24		
		1	6.00	5.00	0.15	4.50		
		1	2.00	2.00	0.15	0.60		
		1	1.00	1.00	0.15	0.15		
		1	0.80	4.00	0.15	0.48		
		1	2.00	2.00	0.15	0.60		
11th Cross		1	3.00	2.00	0.15	0.90		
		1	4.00	0.80	0.15	0.48		
		1	2.20	8.00	0.15	2.64		
		1	5.00	2.00	0.15	1.50		

			1	2.00	4.00	0.15	1.20		
			1	4.00	2.00	0.15	1.20		
			1	2.00	2.00	0.15	0.60		
			1	8.00	1.00	0.15	1.20		
			1	10.00	8.00	0.15	12.00		
			1	3.00	1.00	0.15	0.45		
			1	2.00	7.00	0.15	2.10		
			1	4.00	2.00	0.15	1.20		
10th Cross			1	2.00	4.00	0.15	1.20		
			1	1.00	1.00	0.15	0.15		
			1	2.00	9.00	0.15	2.70		
			1	0.60	0.60	0.15	0.05		
			1	2.00	5.00	0.15	1.50		
			1	5.00	4.00	0.15	3.00		
			1	5.00	5.00	0.15	3.75		
			1	2.00	1.00	0.15	0.30		
			1	2.00	2.00	0.15	0.60		
9th Cross			1	4.00	6.00	0.15	3.60		
			1	5.00	1.00	0.15	0.75		
			1	0.90	0.90	0.15	0.12		
			1	2.00	1.00	0.15	0.30		
			1	6.00	1.50	0.15	1.35		
			1	10.00	1.00	0.15	1.50		
			1	5.00	2.00	0.15	1.50		
			1	4.80	1.90	0.15	1.37		
			1	10.00	2.00	0.15	3.00		
			1	2.50	2.80	0.15	1.05		
8th Cross			1	3.30	1.50	0.15	0.74		
			1	6.50	1.00	0.15	0.98		
			1	6.50	9.00	0.15	8.78		
			1	6.50	1.00	0.15	0.98		
			1	1.00	1.00	0.15	0.15		
			1	0.80	3.00	0.15	0.36		
			1	10.00	0.50	0.15	0.75		
			1	6.00	1.00	0.15	0.90		
			1	6.00	5.00	0.15	4.50		
			1	6.00	1.10	0.15	0.99		
			1	1.00	7.00	0.15	1.05		
			1	4.00	6.90	0.15	4.14		
			1	1.90	2.00	0.15	0.57		
			1	2.00	2.00	0.15	0.60		
			1	2.00	1.10	0.15	0.33		
			1	1.00	4.00	0.15	0.60		
			1	6.50	0.90	0.15	0.88		
6th Cross			1	1.30	1.50	0.15	0.29		
			1	5.00	2.00	0.15	1.50		
			1	6.00	0.80	0.15	0.72		
			1	3.00	1.00	0.15	0.45		
			1	6.00	0.80	0.15	0.72		
			1	2.00	1.00	0.15	0.30		
			1	6.50	0.80	0.15	0.78		
			1	2.00	1.00	0.15	0.30		
			1	1.00	1.00	0.15	0.15		
			1	2.00	1.00	0.15	0.30		
			1	6.00	0.90	0.15	0.81		

			1	6.00	1.00	0.15	0.90		
			1	4.00	3.50	0.15	2.10		
	7th Cross		1	1.00	1.00	0.15	0.15		
			1	6.50	1.60	0.15	1.56		
			1	6.00	0.80	0.15	0.72		
			1	2.00	1.00	0.15	0.30		
			1	5.00	0.80	0.15	0.60		
			1	3.00	1.00	0.15	0.45		
			1	0.60	0.80	0.15	0.07		
			1	6.50	0.80	0.15	0.78		
	5th Cross		1	1.00	1.50	0.15	0.23		
			1	2.00	1.00	0.15	0.30		
			1	6.00	0.90	0.15	0.81		
			1	6.00	1.20	0.15	1.08		
			1	1.00	1.00	0.15	0.15		
			1	2.00	1.00	0.15	0.30		
			1	6.50	0.80	0.15	0.78		
			1	6.50	0.90	0.15	0.88		
			1	6.50	0.60	0.15	0.59		
			1	6.00	1.00	0.15	0.90		
	4th Cross		1	6.00	1.20	0.15	1.08		
			1	1.00	1.50	0.15	0.23		
			1	2.00	1.00	0.15	0.30		
			1	6.00	0.90	0.15	0.81		
			1	6.00	0.90	0.15	0.81		
			1	6.00	1.20	0.15	1.08		
			1	1.00	1.00	0.15	0.15		
			1	6.00	0.70	0.15	0.63		
			1	6.00	0.50	0.15	0.45		
			1	2.00	1.80	0.15	0.54		
			1	6.00	0.55	0.15	0.50		
			1	6.00	0.70	0.15	0.63		
	3rd Cross		1	12.00	0.35	0.15	0.63		
			1	6.00	0.45	0.15	0.41		
			1	6.00	0.60	0.15	0.54		
			1	1.00	1.20	0.15	0.18		
			1	4.50	1.80	0.15	1.22		
			1	2.00	2.00	0.15	0.60		
			1	5.00	3.50	0.15	2.63		
			1	5.00	2.00	0.15	1.50		
			1	1.00	1.00	0.15	0.15		
			1	6.00	1.50	0.15	1.35		
	2nd Cross		1	5.50	5.00	0.15	4.13		
			1	10.00	5.00	0.15	7.50		
			1	6.00	0.90	0.15	0.81		
			1	1.00	1.00	0.15	0.15		
			1	6.00	0.80	0.15	0.72		
			1	3.00	2.00	0.15	0.90		
	st Cross		1	6.00	0.80	0.15	0.72		
			1	1.00	1.00	0.15	0.15		
			1	6.00	0.90	0.15	0.81		
			1	6.00	3.00	0.15	2.70		
			1	6.00	0.70	0.15	0.63		
			1	6.00	0.60	0.15	0.54		
			1	6.00	0.50	0.15	0.45		

		1	2.00	1.90	0.15	0.57		
		1	6.00	0.50	0.15	0.45		
		1	2.00	1.90	0.15	0.57		
		1	6.00	0.50	0.15	0.45		
		1	6.00	0.60	0.15	0.54		
		1	2.00	2.00	0.15	0.60		
		1	6.00	0.70	0.15	0.63		
		1	3.00	1.00	0.15	0.45		
		1	6.00	0.60	0.15	0.54		
		1	6.00	0.75	0.15	0.68		
		1	2.00	1.00	0.15	0.30		
		1	6.00	0.65	0.15	0.59		
		1	6.00	0.50	0.15	0.45		
		1	6.00	0.60	0.15	0.54		
Shivaramakaranthnagar		1	1.00	1.00	0.15	0.15		
		1	2.00	1.20	0.15	0.36		
		1	3.00	1.00	0.15	0.45		
		1	1.00	1.00	0.15	0.15		
		1	2.00	1.00	0.15	0.30		
		1	3.20	2.00	0.15	0.96		
		1	1.00	1.00	0.15	0.15		
		1	0.50	0.50	0.15	0.04		
		1	0.60	0.60	0.15	0.05		
		1	1.00	1.00	0.15	0.15		
		1	1.00	1.50	0.15	0.23		
Vinayakanagara 1st Cross		1	1.50	6.00	0.15	1.35		
		1	3.10	6.00	0.15	2.79		
		1	1.10	3.10	0.15	0.51		
		1	2.00	3.00	0.15	0.90		
		1	2.10	2.20	0.15	0.69		
		1	1.20	6.10	0.15	1.10		
		1	1.80	1.10	0.15	0.30		
		1	0.80	5.00	0.15	0.60		
		1	2.00	3.00	0.15	0.90		
2nd Cross		1	6.20	0.90	0.15	0.84		
		1	3.00	4.00	0.15	1.80		
		1	6.00	0.90	0.15	0.81		
		1	2.25	3.20	0.15	1.08		
		1	3.00	0.90	0.15	0.41		
		1	2.10	0.90	0.15	0.28		
2nd Main Road		1	8.00	2.10	0.15	2.52		
		1	6.00	0.80	0.15	0.72		
		1	4.00	0.85	0.15	0.51		
		1	4.00	3.00	0.15	1.80		
		1	3.00	2.00	0.15	0.90		
		1	4.00	2.50	0.15	1.50		
		1	3.30	2.70	0.15	1.34		
		1	2.20	1.10	0.15	0.36		
		1	2.70	1.80	0.15	0.73		
3rd Cross		1	2.00	0.80	0.15	0.24		
		1	3.20	3.30	0.15	1.58		
		1	3.20	2.00	0.15	0.96		
		1	2.00	1.80	0.15	0.54		
		1	4.20	3.80	0.15	2.39		
		1	2.10	2.00	0.15	0.63		

			1	5.20	0.80	0.15	0.62		
			1	5.10	0.60	0.15	0.46		
			1	3.20	1.20	0.15	0.58		
			1	6.00	2.10	0.15	1.89		
			1	3.20	2.00	0.15	0.96		
			1	2.20	1.80	0.15	0.59		
	kattigenahalli to Kogilu Road		1	2.20	2.10	0.15	0.69		
			1	12.00	6.00	0.15	10.80		
			1	2.00	1.80	0.15	0.54		
			1	1.00	1.10	0.15	0.17		
	Shivashankar layout		1	2.00	0.80	0.15	0.24		
			1	3.00	2.80	0.15	1.26		
			1	6.00	0.80	0.15	0.72		
			1	5.00	0.60	0.15	0.45		
			1	5.00	1.10	0.15	0.83		
			1	2.00	1.00	0.15	0.30		
			1	5.00	0.80	0.15	0.60		
			1	6.00	0.60	0.15	0.54		
			1	5.00	0.80	0.15	0.60		
	Bhoomika Realestate		1	6.00	0.80	0.15	0.72		
			1	3.00	1.00	0.15	0.45		
			1	2.00	2.00	0.15	0.60		
			1	5.00	2.00	0.15	1.50		
	Railway track Palanahalli Road		1	1.00	2.00	0.15	0.30		
			1	2.00	2.50	0.15	0.75		
			1	1.50	1.50	0.15	0.34		
			1	5.00	1.00	0.15	0.75		
			1	1.00	1.00	0.15	0.15		
			1	5.00	2.00	0.15	1.50		
			1	3.00	2.00	0.15	0.90		
			1	1.00	2.00	0.15	0.30		
			1	1.00	1.00	0.15	0.15		
			1	1.50	1.20	0.15	0.27		
			1	1.20	1.00	0.15	0.18		
			1	1.10	1.20	0.15	0.20		
			1	0.90	0.80	0.15	0.11		
			1	1.00	1.00	0.15	0.15		
	10th Cross SRK Nagara 2nd Stage		1	3.00	2.00	0.15	0.90		
			1	2.00	1.00	0.15	0.30		
			1	5.00	3.00	0.15	2.25		
			1	2.00	2.00	0.15	0.60		
			1	5.00	3.00	0.15	2.25		
			1	1.00	1.00	0.15	0.15		
			1	1.50	1.80	0.15	0.41		
			1	2.00	2.00	0.15	0.60		
			1	1.00	1.00	0.15	0.15		
	2nd Cross SRK Nagara		1	5.00	1.00	0.15	0.75		
			1	3.00	2.00	0.15	0.90		
			1	5.00	0.90	0.15	0.68		
			1	5.00	0.80	0.15	0.60		
			1	5.00	2.00	0.15	1.50		
			1	1.00	1.00	0.15	0.15		
			1	0.50	0.90	0.15	0.07		
			1	5.00	1.00	0.15	0.75		

			1	2.00	1.00	0.15	0.30		
			1	3.00	2.00	0.15	0.90		
			1	2.00	2.00	0.15	0.60		
	2nd Main Road		1	3.00	1.00	0.15	0.45		
			1	1.50	1.00	0.15	0.23		
			1	6.00	0.80	0.15	0.72		
			1	3.00	3.20	0.15	1.44		
	3rd Main Road		1	5.00	0.60	0.15	0.45		
			1	5.00	0.80	0.15	0.60		
			1	1.20	5.00	0.15	0.90		
			1	5.20	2.00	0.15	1.56		
			1	8.10	0.80	0.15	0.97		
	Chokkanahalli Village Road		1	10.00	1.20	0.15	1.80		
			1	3.00	5.00	0.15	2.25		
			1	2.00	1.00	0.15	0.30		
			1	6.80	1.20	0.15	1.22		
			1	2.00	2.00	0.15	0.60		
			1	3.20	1.50	0.15	0.72		
			1	0.80	0.80	0.15	0.10		
			1	1.00	0.90	0.15	0.14		
			1	3.00	2.80	0.15	1.26		
			1	10.00	5.20	0.15	7.80		
			1	1.50	2.00	0.15	0.45		
			1	1.60	2.00	0.15	0.48		
			1	1.00	1.80	0.15	0.27		
			1	3.00	3.00	0.15	1.35		
			1	2.00	3.00	0.15	0.90		
			1	3.00	5.00	0.15	2.25		
	Thirumenahalli Road		1	5.00	6.00	0.15	4.50		
			1	2.00	1.00	0.15	0.30		
			1	5.00	0.90	0.15	0.68		
			1	5.00	0.60	0.15	0.45		
			1	5.00	0.75	0.15	0.56		
			1	7.00	1.10	0.15	1.16		
			1	1.50	1.00	0.15	0.23		
			1	2.00	2.10	0.15	0.63		
	Srirampura Village Cross Road up to 6th Main		1	1.00	0.50	0.15	0.08		
			1	1.00	1.00	0.15	0.15		
			1	2.00	2.00	0.15	0.60		
			1	5.00	2.00	0.15	1.50		
			1	2.00	2.00	0.15	0.60		
			1	2.00	1.00	0.15	0.30		
			1	3.00	1.00	0.15	0.45		
			1	4.50	1.00	0.15	0.68		
	Datta layout		1	5.00	0.80	0.15	0.60		
			1	5.20	0.70	0.15	0.55		
			1	5.10	0.80	0.15	0.61		
	kalidasa layout Main Road		1	1.00	0.80	0.15	0.12		
			1	5.00	0.60	0.15	0.45		
			1	3.50	2.00	0.15	1.05		
			1	3.00	2.80	0.15	1.26		
			1	2.00	0.90	0.15	0.27		
			1	5.00	0.60	0.15	0.45		
			1	9.00	1.20	0.15	1.62		
			1	8.00	2.30	0.15	2.76		

		1	3.10	0.70	0.15	0.33		
		1	4.00	2.00	0.15	1.20		
		1	3.50	2.00	0.15	1.05		
		1	2.00	1.10	0.15	0.33		
		1	5.10	0.60	0.15	0.46		
		1	4.50	0.60	0.15	0.41		
Kattigenahalli Road		1	3.80	0.75	0.15	0.43		
		1	2.00	1.00	0.15	0.30		
		1	3.00	2.00	0.15	0.90		
		1	9.00	5.00	0.15	6.75		
		1	9.00	5.00	0.15	6.75		
		1	2.00	2.00	0.15	0.60		
		1	3.20	2.10	0.15	1.01		
Palanahalli lake Road		1	7.00	0.90	0.15	0.95		
		1	7.00	1.10	0.15	1.16		
		1	2.00	2.00	0.15	0.60		
		1	7.00	1.10	0.15	1.16		
		1	7.00	0.90	0.15	0.95		
kattigenahalli 1st Cross		1	2.00	1.00	0.15	0.30		
		1	2.00	2.00	0.15	0.60		
		1	2.00	2.80	0.15	0.84		
		1	3.00	1.80	0.15	0.81		
		1	3.00	1.90	0.15	0.86		
		1	9.00	1.80	0.15	2.43		
		1	2.00	0.90	0.15	0.27		
		1	8.00	3.10	0.15	3.72		
		1	9.00	2.00	0.15	2.70		
		1	4.00	0.70	0.15	0.42		
		1	15.00	3.10	0.15	6.98		
		1	12.00	4.00	0.15	7.20		
		1	4.00	2.80	0.15	1.68		
		1	8.00	3.10	0.15	3.72		
		1	7.00	2.00	0.15	2.10		
		1	4.00	0.70	0.15	0.42		
		1	15.00	3.10	0.15	6.98		
		1	10.00	2.00	0.15	3.00		
		1	4.00	2.80	0.15	1.68		
kalidas layout		1	2.00	2.00	0.15	0.60		
		1	3.00	1.80	0.15	0.81		
		1	2.00	3.20	0.15	0.96		
		1	3.10	2.80	0.15	1.30		
		1	2.20	0.80	0.15	0.26		
Bharathnagara Main Road		1	9.00	2.50	0.15	3.38		
		1	10.00	6.00	0.15	9.00		
		1	2.00	2.00	0.15	0.60		
		1	3.00	4.00	0.15	1.80		
		1	3.00	0.90	0.15	0.41		
		1	3.20	3.10	0.15	1.49		
		1	4.00	2.20	0.15	1.32		
		1	5.00	0.90	0.15	0.68		
Cross Roads		1	5.00	0.60	0.15	0.45		
		1	3.00	2.00	0.15	0.90		
		1	4.00	1.80	0.15	1.08		
		1	7.00	5.00	0.15	5.25		
		1	5.00	0.90	0.15	0.68		

		1	13.00	1.00	0.15	1.95		
		1	1.80	2.00	0.15	0.54		
		1	5.00	0.90	0.15	0.68		
		1	0.60	5.00	0.15	0.45		
		1	3.00	2.00	0.15	0.90		
		1	1.80	3.00	0.15	0.81		
		1	5.00	8.00	0.15	6.00		
Anjanadri Layout		1	2.00	3.00	0.15	0.90		
		1	3.00	2.00	0.15	0.90		
Babanagara		1	0.80	5.00	0.15	0.60		
		1	3.00	1.00	0.15	0.45		
		1	2.00	1.00	0.15	0.30		
Nirantara layout		1	2.00	1.10	0.15	0.33		
		1	5.00	1.10	0.15	0.83		
		1	5.00	0.60	0.15	0.45		
		1	3.00	0.60	0.15	0.27		
		1	5.00	0.90	0.15	0.68		
		1	5.00	1.50	0.15	1.13		
		1	10.00	1.90	0.15	2.85		
		1	5.00	1.10	0.15	0.83		
		1	3.00	0.90	0.15	0.41		
		1	3.00	2.00	0.15	0.90		
		1	5.00	2.00	0.15	1.50		
		1	2.00	2.00	0.15	0.60		
		1	4.00	0.80	0.15	0.48		
		1	3.00	2.80	0.15	1.26		
Basavalingappa nagara		1	2.00	3.20	0.15	0.96		
		1	1.00	2.80	0.15	0.42		
		1	2.20	0.80	0.15	0.26		
		1	9.00	2.50	0.15	3.38		
		1	2.00	6.00	0.15	1.80		
		1	2.00	2.00	0.15	0.60		
		1	3.00	0.80	0.15	0.36		
		1	3.00	1.20	0.15	0.54		
		1	1.00	1.00	0.15	0.15		
		1	2.00	1.00	0.15	0.30		
		1	3.00	0.80	0.15	0.36		
		1	2.00	1.00	0.15	0.30		
		1	1.00	1.00	0.15	0.15		
		1	1.00	1.00	0.15	0.15		
		1	2.00	0.90	0.15	0.27		
		1	1.00	1.00	0.15	0.15		
		1	1.00	3.50	0.15	0.53		
		1	1.00	1.00	0.15	0.15		
		1	2.00	1.60	0.15	0.48		
		1	2.00	0.80	0.15	0.24		
		1	2.00	1.00	0.15	0.30		
		1	3.00	2.30	0.15	1.04		
		1	3.10	0.70	0.15	0.33		
		1	2.00	1.00	0.15	0.30		
		1	2.00	0.80	0.15	0.24		
		1	2.00	1.00	0.15	0.30		
		1	1.00	1.00	0.15	0.15		
Balaji layout Main Road		1	1.00	1.00	0.15	0.15		
		1	2.00	0.90	0.15	0.27		

			1	3.00	3.50	0.15	0.15		
			1	1.00	1.00	0.15	1.58		
			1	2.00	1.60	0.15	0.15		
			1	1.00	0.80	0.15	0.48		
			1	2.00	1.00	0.15	0.12		
			1	1.00	1.20	0.15	0.30		
			1	2.00	0.80	0.15	0.18		
	Cross Roads		1	1.00	1.20	0.15	0.24		
			1	1.00	1.00	0.15	0.18		
			1	1.00	1.00	0.15	0.15		
			1	2.00	0.80	0.15	0.15		
			1	1.00	1.00	0.15	0.24		
			1	2.00	1.00	0.15	0.15		
			1	4.00	3.50	0.15	0.30		
	5th Cross		1	2.00	1.00	0.15	2.10		
			1	1.00	1.60	0.15	0.30		
			1	1.00	0.80	0.15	0.24		
			1	2.00	1.00	0.15	0.12		
			1	1.00	0.80	0.15	0.30		
			1	3.00	1.20	0.15	0.12		
			1	3.00	1.00	0.15	0.54		
			1	3.00	1.00	0.15	0.45		
			1	2.00	0.80	0.15	0.45		
			1	1.00	1.00	0.15	0.24		
			1	1.00	1.00	0.15	0.15		
	7th Cross		1	1.00	1.00	0.15	0.15		
			1	2.00	1.60	0.15	0.15		
			1	1.00	0.80	0.15	0.48		
			1	2.00	1.00	0.15	0.12		
			1	2.00	2.00	0.15	0.30		
			1	3.00	2.00	0.15	0.60		
			1	3.50	3.00	0.15	0.90		
			1	1.00	4.00	0.15	1.58		
	11th Cross		1	1.80	2.00	0.15	0.60		
			1	1.00	1.00	0.15	0.54		
			1	3.00	2.00	0.15	0.15		
			1	3.00	0.00	0.15	0.90		
			1	1.00	1.00	0.15	0.00		
	Sampigehalli to Agrahara Layout		1	2.00	2.00	0.15	0.15		
			1	3.50	2.00	0.15	0.60		
			1	2.00	1.00	0.15	1.05		
			1	1.80	2.00	0.15	0.30		
			1	1.00	3.00	0.15	0.54		
			1	1.20	2.00	0.15	0.45		
			1	1.00	2.00	0.15	0.36		
			1	1.20	3.00	0.15	0.30		
			1	1.30	2.00	0.15	0.54		
			1	3.10	1.00	0.15	0.39		
			1	2.00	5.00	0.15	0.47		
							1.50		
							552.70	**2001.28**	**1106099.00**
	Basic Rate	1888.00							
	Area Weightage @ 6%	113.28							
	Total	2001.28							

1	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 502.0 back filling the pot hole with bituminous material as per clause 500.4 compacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications MORTH Specification (Page No. 247/Itm No.35.5) PWD SR 2018-19						Sqm		
	Shrampura Main Road Up to Railway Gate		1	3.00	2.00		6.00		
			1	5.00	1.80		9.00		
			1	5.00	2.80		14.00		
			1	6.00	2.50		15.00		
			1	5.00	1.00		5.00		
			1	1.00	2.15		2.15		
			1	6.00	1.20		7.20		
			1	5.00	3.00		15.00		
			1	5.00	5.00		25.00		
			1	6.00	1.00		6.00		
			1	2.00	1.20		2.40		
	Royal Enclave		1	1.00	1.00		1.00		
			1	6.00	2.00		12.00		
			1	2.00	2.00		4.00		
			1	1.00	1.75		1.75		
			1	5.00	2.00		10.00		
	12th A Cross		1	2.00	8.00		16.00		
			1	3.20	1.75		5.60		
	Jakkur 1st Cross and 2nd Cross		1	1.00	1.75		1.75		
			1	1.00	1.50		1.50		
			1	5.00	2.20		11.00		
			1	5.00	0.60		3.00		
			1	2.00	7.00		14.00		
	Govt School Road		1	1.00	1.00		1.00		
			1	2.00	2.00		4.00		
			1	4.50	1.00		4.50		
			1	2.00	1.90		3.80		
			1	2.00	1.90		3.80		
			1	1.00	1.00		1.00		
			1	3.00	1.00		3.00		
			1	2.00	1.00		2.00		
	Telelcom layout 15th Cross		1	5.00	0.09		0.45		
			1	6.00	4.00		24.00		
			1	1.00	1.00		1.00		
			1	5.00	3.00		15.00		
			1	3.00	4.50		13.50		
			1	4.00	4.80		19.20		
	2nd Main Road		1	8.00	9.00		72.00		
			1	3.00	5.20		15.60		
			1	4.60	2.30		10.58		
			1	2.00	1.00		2.00		
			1	4.00	5.00		20.00		
			1	8.00	4.00		32.00		
			1	8.00	2.00		16.00		
	14th Cross		1	10.00	2.00		20.00		
			1	4.00	5.00		20.00		

		1	2.00	2.00		4.00			
		1	10.00	1.00		10.00			
		1	2.00	2.00		4.00			
		1	5.20	3.00		15.60			
		1	3.00	2.00		6.00			
		1	8.00	1.10		8.80			
		1	5.00	0.90		4.50			
		1	2.00	6.00		12.00			
13th Cross		1	6.50	0.90		5.85			
		1	7.50	0.80		6.00			
		1	3.00	2.00		6.00			
		1	1.00	1.00		1.00			
		1	4.00	2.00		8.00			
		1	4.00	2.00		8.00			
		1	2.00	8.00		16.00			
		1	5.00	1.00		5.00			
		1	7.00	9.00		63.00			
12th Cross		1	3.00	0.80		2.40			
		1	2.00	0.80		1.60			
		1	6.00	5.00		30.00			
		1	2.00	2.00		4.00			
		1	1.00	1.00		1.00			
		1	0.80	4.00		3.20			
		1	2.00	2.00		4.00			
11th Cross		1	3.00	2.00		6.00			
		1	4.00	0.80		3.20			
		1	2.20	8.00		17.60			
		1	5.00	2.00		10.00			
		1	2.00	4.00		8.00			
		1	4.00	2.00		8.00			
		1	2.00	2.00		4.00			
		1	8.00	1.00		8.00			
		1	10.00	8.00		80.00			
		1	3.00	1.00		3.00			
		1	2.00	7.00		14.00			
		1	4.00	2.00		8.00			
		1	2.00	4.00		8.00			
10th Cross		1	1.00	1.00		1.00			
		1	2.00	9.00		18.00			
		1	0.60	0.60		0.36			
		1	2.00	5.00		10.00			
		1	5.00	4.00		20.00			
		1	5.00	5.00		25.00			
		1	2.00	1.00		2.00			
		1	2.00	2.00		4.00			
		1	4.00	6.00		24.00			
9th Cross		1	5.00	1.00		5.00			
		1	0.90	0.90		0.81			
		1	2.00	1.00		2.00			
		1	6.00	1.50		9.00			
		1	10.00	1.00		10.00			
		1	5.00	2.00		10.00			
		1	4.80	1.90		9.12			
		1	10.00	2.00		20.00			
		1	2.50	2.80		7.00			

	8th Cross		1	3.30	1.50		4.95			
			1	6.50	1.00		6.50			
			1	6.50	9.00		58.50			
			1	6.50	1.00		6.50			
			1	1.00	1.00		1.00			
			1	0.80	3.00		2.40			
			1	10.00	0.50		5.00			
			1	6.00	1.00		6.00			
			1	6.00	5.00		30.00			
			1	6.00	1.10		6.60			
			1	1.00	7.00		7.00			
			1	4.00	6.90		27.60			
			1	1.90	2.00		3.80			
			1	2.00	2.00		4.00			
			1	2.00	1.10		2.20			
			1	1.00	4.00		4.00			
	6th Cross		1	6.50	0.90		5.85			
			1	1.30	1.50		1.95			
			1	5.00	2.00		10.00			
			1	6.00	0.80		4.80			
			1	3.00	1.00		3.00			
			1	6.00	0.80		4.80			
			1	2.00	1.00		2.00			
			1	6.50	0.80		5.20			
			1	2.00	1.00		2.00			
			1	1.00	1.00		1.00			
			1	2.00	1.00		2.00			
			1	6.00	0.90		5.40			
			1	6.00	1.00		6.00			
			1	4.00	3.50		14.00			
	7th Cross		1	1.00	1.00		1.00			
			1	6.50	1.60		10.40			
			1	6.00	0.80		4.80			
			1	2.00	1.00		2.00			
			1	5.00	0.80		4.00			
			1	3.00	1.00		3.00			
			1	0.60	0.80		0.48			
			1	6.50	0.80		5.20			
	5th Cross		1	1.00	1.50		1.50			
			1	2.00	1.00		2.00			
			1	6.00	0.90		5.40			
			1	6.00	1.20		7.20			
			1	1.00	1.00		1.00			
			1	2.00	1.00		2.00			
			1	6.50	0.80		5.20			
			1	6.50	0.90		5.85			
			1	6.50	0.60		3.90			
			1	6.00	1.00		6.00			
	4th Cross		1	6.00	1.20		7.20			
			1	1.00	1.50		1.50			
			1	2.00	1.00		2.00			
			1	6.00	0.90		5.40			
			1	6.00	0.90		5.40			
			1	6.00	1.20		7.20			
			1	1.00	1.00		1.00			

		1	6.00	0.70		4.20		
		1	6.00	0.50		3.00		
		1	2.00	1.80		3.60		
		1	6.00	0.55		3.30		
		1	6.00	0.70		4.20		
3rd Cross		1	12.00	0.35		4.20		
		1	6.00	0.45		2.70		
		1	6.00	0.60		3.60		
		1	1.00	1.20		1.20		
		1	4.50	1.80		8.10		
		1	2.00	2.00		4.00		
		1	5.00	3.50		17.50		
		1	5.00	2.00		10.00		
		1	1.00	1.00		1.00		
		1	6.00	1.50		9.00		
2nd Cross		1	5.50	5.00		27.50		
		1	10.00	5.00		50.00		
		1	6.00	0.90		5.40		
		1	1.00	1.00		1.00		
		1	6.00	0.80		4.80		
		1	3.00	2.00		6.00		
1st Cross		1	6.00	0.80		4.80		
		1	1.00	1.00		1.00		
		1	6.00	0.90		5.40		
		1	6.00	3.00		18.00		
		1	6.00	0.70		4.20		
		1	6.00	0.60		3.60		
		1	6.00	0.50		3.00		
		1	2.00	1.90		3.80		
		1	6.00	0.50		3.00		
		1	2.00	1.90		3.80		
		1	6.00	0.50		3.00		
		1	6.00	0.60		3.60		
		1	2.00	2.00		4.00		
		1	6.00	0.70		4.20		
		1	3.00	1.00		3.00		
		1	6.00	0.60		3.60		
		1	6.00	0.75		4.50		
		1	2.00	1.00		2.00		
		1	6.00	0.65		3.90		
		1	6.00	0.50		3.00		
		1	6.00	0.60		3.60		
Shivaramakaranthnagar		1	1.00	1.00		1.00		
		1	2.00	1.20		2.40		
		1	3.00	1.00		3.00		
		1	1.00	1.00		1.00		
		1	2.00	1.00		2.00		
		1	3.20	2.00		6.40		
		1	1.00	1.00		1.00		
		1	0.50	0.50		0.25		
		1	0.60	0.60		0.36		
		1	1.00	1.00		1.00		
		1	1.00	1.50		1.50		
Vinayakanagara 1st Cross		1	1.50	6.00		9.00		
		1	3.10	6.00		18.60		

			1	1.10	3.10		3.41		
			1	2.00	3.00		6.00		
			1	2.10	2.20		4.62		
			1	1.20	6.10		7.32		
			1	1.80	1.10		1.98		
			1	0.80	5.00		4.00		
			1	2.00	3.00		6.00		
	2nd Cross		1	6.20	0.90		5.58		
			1	3.00	4.00		12.00		
			1	6.00	0.90		5.40		
			1	2.25	3.20		7.20		
			1	3.00	0.90		2.70		
			1	2.10	0.90		1.89		
	2nd Main Road		1	8.00	2.10		16.80		
			1	6.00	0.80		4.80		
			1	4.00	0.85		3.40		
			1	4.00	3.00		12.00		
			1	3.00	2.00		6.00		
			1	4.00	2.50		10.00		
			1	3.30	2.70		8.91		
			1	2.20	1.10		2.42		
	3rd Cross		1	2.70	1.80		4.86		
			1	2.00	0.80		1.60		
			1	3.20	3.30		10.56		
			1	3.20	2.00		6.40		
			1	2.00	1.80		3.60		
			1	4.20	3.80		15.96		
			1	2.10	2.00		4.20		
			1	5.20	0.80		4.16		
			1	5.10	0.60		3.06		
			1	3.20	1.20		3.84		
			1	6.00	2.10		12.60		
			1	3.20	2.00		6.40		
			1	2.20	1.80		3.96		
			1	2.20	2.10		4.62		
	kattigenahalli to Kogilu Road		1	12.00	6.00		72.00		
			1	2.00	1.80		3.60		
			1	1.00	1.10		1.10		
			1	2.00	0.80		1.60		
	Shivashankar layout		1	3.00	2.80		8.40		
			1	6.00	0.80		4.80		
			1	5.00	0.60		3.00		
			1	5.00	1.10		5.50		
			1	2.00	1.00		2.00		
			1	5.00	0.80		4.00		
			1	6.00	0.60		3.60		
			1	5.00	0.80		4.00		
			1	6.00	0.80		4.80		
	Bhoomika Realestate		1	3.00	1.00		3.00		
			1	2.00	2.00		4.00		
			1	5.00	2.00		10.00		
	Railway track Palanahalli Road		1	1.00	2.00		2.00		
			1	2.00	2.50		5.00		
			1	1.50	1.50		2.25		
			1	5.00	1.00		5.00		

	1	1.00	1.00		1.00		
	1	5.00	2.00		10.00		
	1	3.00	2.00		6.00		
	1	1.00	2.00		2.00		
	1	1.00	1.00		1.00		
	1	1.50	1.20		1.80		
	1	1.20	1.00		1.20		
	1	1.10	1.20		1.32		
	1	0.90	0.80		0.72		
	1	1.00	1.00		1.00		
10th Cross SPK Nagara 2nd Stage	1	3.00	2.00		6.00		
	1	2.00	1.00		2.00		
	1	5.00	3.00		15.00		
	1	2.00	2.00		4.00		
	1	5.00	3.00		15.00		
	1	1.00	1.00		1.00		
	1	1.50	1.80		2.70		
	1	2.00	2.00		4.00		
	1	1.00	1.00		1.00		
2nd Cross SPK Nagara	1	5.00	1.00		5.00		
	1	3.00	2.00		6.00		
	1	5.00	0.90		4.50		
	1	5.00	0.80		4.00		
	1	5.00	2.00		10.00		
	1	1.00	1.00		1.00		
	1	0.50	0.90		0.45		
	1	5.00	1.00		5.00		
	1	2.00	1.00		2.00		
	1	3.00	2.00		6.00		
	1	2.00	2.00		4.00		
	1	3.00	1.00		3.00		
	1	1.50	1.00		1.50		
2nd Main Road	1	6.00	0.80		4.80		
	1	3.00	3.20		9.60		
	1	5.00	0.60		3.00		
	1	5.00	0.80		4.00		
3rd Main Road	1	1.20	5.00		6.00		
	1	5.20	2.00		10.40		
	1	8.10	0.80		6.48		
	1	10.00	1.20		12.00		
	1	3.00	5.00		15.00		
Doddanekkundi Village Road	1	2.00	1.00		2.00		
	1	6.80	1.20		8.16		
	1	2.00	2.00		4.00		
	1	3.20	1.50		4.80		
	1	0.80	0.80		0.64		
	1	1.00	0.90		0.90		
	1	3.00	2.80		8.40		
	1	10.00	5.20		52.00		
	1	1.50	2.00		3.00		
	1	1.80	2.00		3.20		
	1	1.00	1.80		1.80		
	1	3.00	3.00		9.00		
	1	2.00	3.00		6.00		
	1	3.00	5.00		15.00		

Thirumenahalli Road		1	5.00	6.00		30.00		
		1	2.00	1.00		2.00		
		1	5.00	0.90		4.50		
		1	5.00	0.60		3.00		
		1	5.00	0.75		3.75		
		1	7.00	1.10		7.70		
		1	1.50	1.00		1.50		
Shrampura Village Cross Road Up to 6th Main		1	2.00	2.10		4.20		
		1	1.00	0.50		0.50		
		1	1.00	1.00		1.00		
		1	2.00	2.00		4.00		
		1	5.00	2.00		10.00		
		1	2.00	2.00		4.00		
		1	2.00	1.00		2.00		
		1	3.00	1.00		3.00		
Datta layout		1	4.50	1.00		4.50		
		1	5.00	0.80		4.00		
		1	5.20	0.70		3.64		
kalidasa layout Main Road		1	5.10	0.80		4.08		
		1	1.00	0.80		0.80		
		1	5.00	0.60		3.00		
		1	3.50	2.00		7.00		
		1	3.00	2.80		8.40		
		1	2.00	0.90		1.80		
		1	5.00	0.60		3.00		
		1	9.00	1.20		10.80		
		1	8.00	2.30		18.40		
		1	3.10	0.70		2.17		
		1	4.00	2.00		8.00		
		1	3.50	2.00		7.00		
		1	2.00	1.10		2.20		
		1	5.10	0.60		3.06		
		1	4.50	0.60		2.70		
		1	3.80	0.75		2.85		
Kattigenahalli Road		1	2.00	1.00		2.00		
		1	3.00	2.00		6.00		
		1	9.00	5.00		45.00		
		1	9.00	5.00		45.00		
		1	2.00	2.00		4.00		
		1	3.20	2.10		6.72		
Palanahalli lake Road		1	7.00	0.90		6.30		
		1	7.00	1.10		7.70		
		1	2.00	2.00		4.00		
		1	7.00	1.10		7.70		
		1	7.00	0.90		6.30		
kattigenahalli 1st Cross		1	2.00	1.00		2.00		
		1	2.00	2.00		4.00		
		1	2.00	2.80		5.60		
		1	3.00	1.80		5.40		
		1	3.00	1.90		5.70		
		1	9.00	1.80		16.20		
		1	2.00	0.90		1.80		
		1	8.00	3.10		24.80		
		1	9.00	2.00		18.00		
		1	4.00	0.70		2.80		

			1	15.00	3.10		46.50		
			1	12.00	4.00		48.00		
			1	4.00	2.80		11.20		
			1	8.00	3.10		24.80		
			1	7.00	2.00		14.00		
			1	4.00	0.70		2.80		
			1	15.00	3.10		46.50		
			1	10.00	2.00		20.00		
	kalidas layout		1	4.00	2.80		11.20		
			1	2.00	2.00		4.00		
			1	3.00	1.80		5.40		
			1	2.00	3.20		6.40		
			1	3.10	2.80		8.68		
	Bharathnagara Main Road		1	2.20	0.80		1.76		
			1	9.00	2.50		22.50		
			1	10.00	6.00		60.00		
			1	2.00	2.00		4.00		
			1	3.00	4.00		12.00		
			1	3.00	0.90		2.70		
			1	3.20	3.10		9.92		
	Cross Roads		1	4.00	2.20		8.80		
			1	5.00	0.90		4.50		
			1	5.00	0.60		3.00		
			1	3.00	2.00		6.00		
			1	4.00	1.80		7.20		
			1	7.00	5.00		35.00		
			1	5.00	0.90		4.50		
			1	13.00	1.00		13.00		
			1	1.80	2.00		3.60		
			1	5.00	0.90		4.50		
			1	0.60	5.00		3.00		
			1	3.00	2.00		6.00		
			1	1.80	3.00		5.40		
			1	5.00	8.00		40.00		
			1	2.00	3.00		6.00		
	Anjanadri Layout		1	3.00	2.00		6.00		
			1	0.80	5.00		4.00		
	Babanagara		1	3.00	1.00		3.00		
			1	2.00	1.00		2.00		
			1	2.00	1.10		2.20		
	Nirantara layout		1	5.00	1.10		5.50		
			1	5.00	0.60		3.00		
			1	3.00	0.60		1.80		
			1	5.00	0.90		4.50		
			1	5.00	1.50		7.50		
			1	10.00	1.90		19.00		
			1	5.00	1.10		5.50		
			1	3.00	0.90		2.70		
			1	3.00	2.00		6.00		
			1	5.00	2.00		10.00		
			1	2.00	2.00		4.00		
			1	4.00	0.80		3.20		
			1	3.00	2.80		8.40		
	Basavalingappa nagara		1	2.00	3.20		6.40		
			1	1.00	2.80		2.80		

		1	2.20	0.80		1.76			
		1	9.00	2.50		22.50			
		1	2.00	6.00		12.00			
		1	2.00	2.00		4.00			
		1	3.00	0.80		2.40			
		1	3.00	1.20		3.60			
		1	1.00	1.00		1.00			
		1	2.00	1.00		2.00			
		1	3.00	0.80		2.40			
		1	2.00	1.00		2.00			
		1	1.00	1.00		1.00			
		1	1.00	1.00		1.00			
		1	2.00	0.90		1.80			
		1	1.00	1.00		1.00			
		1	1.00	3.50		3.50			
		1	1.00	1.00		1.00			
		1	2.00	1.60		3.20			
		1	2.00	0.80		1.60			
		1	2.00	1.00		2.00			
		1	3.00	2.30		6.90			
		1	3.10	0.70		2.17			
		1	2.00	1.00		2.00			
		1	2.00	0.80		1.60			
		1	2.00	1.00		2.00			
Balaji layout Main Road		1	1.00	1.00		1.00			
		1	1.00	1.00		1.00			
		1	2.00	0.90		1.80			
		1	1.00	1.00		1.00			
		1	3.00	3.50		10.50			
		1	1.00	1.00		1.00			
		1	2.00	1.60		3.20			
		1	1.00	0.80		0.80			
		1	2.00	1.00		2.00			
		1	1.00	1.20		1.20			
		1	2.00	0.80		1.60			
Cross Roads		1	1.00	1.20		1.20			
		1	1.00	1.00		1.00			
		1	1.00	1.00		1.00			
		1	2.00	0.80		1.60			
		1	1.00	1.00		1.00			
		1	2.00	1.00		2.00			
		1	4.00	3.50		14.00			
5th Cross		1	2.00	1.00		2.00			
		1	1.00	1.60		1.60			
		1	1.00	0.80		0.80			
		1	2.00	1.00		2.00			
		1	1.00	0.80		0.80			
		1	3.00	1.20		3.60			
		1	3.00	1.00		3.00			
		1	3.00	1.00		3.00			
		1	2.00	0.80		1.60			
		1	1.00	1.00		1.00			
		1	1.00	1.00		1.00			
7th Cross		1	1.00	1.00		1.00			
		1	2.00	1.60		3.20			

			1	1.00	0.80		0.80		
			1	2.00	1.00		2.00		
			1	2.00	2.00		4.00		
			1	3.00	2.00		6.00		
			1	3.50	3.00		10.50		
	11th Cross		1	1.00	4.00		4.00		
			1	1.80	2.00		3.60		
			1	1.00	1.00		1.00		
			1	3.00	2.00		6.00		
			1	3.00	0.00		0.00		
	Sampigehalli to Agrahara Layout		1	1.00	1.00		1.00		
			1	2.00	2.00		4.00		
			1	3.50	2.00		7.00		
			1	2.00	1.00		2.00		
			1	1.80	2.00		3.60		
			1	1.00	3.00		3.00		
			1	1.20	2.00		2.40		
			1	1.00	2.00		2.00		
			1	1.20	3.00		3.60		
			1	1.30	2.00		2.60		
			1	3.10	1.00		3.10		
			1	2.00	5.00		10.00		
							3684.64	365.70	1347473.00
	Basic Rate	345.00							
	Area Weightage @ 6%	20.70							
	Total	365.70							
							Grand Total		2562932.00
24	For 12% Applicable GST								307552.00
25	For 1% PMC Charges								25629.00
26	KRIDL Charges 3%								76888.00
27	Labour Cess 1%								25629.00
28	Miscesallaneous Charges	L/S							1370.00
								Total	3000000.00

CERTIFICATE

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR 2018-19
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Assistant Engineer

Assistant Executive Engineer
Byatarayanapura Sub Division

Executive Engineer
Byatarayanapura Division

Administrative Approval
Accorded For RS ಮಂಜೂರಾತಿ
Head of A/C ಶೀರ್ಷಿಕೆ
CER NO :...2918..... Dt: 08.02.18

TA to CE (YNK)
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Technical Sanction
Accorded For RS ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ
Head of A/C ಶೀರ್ಷಿಕೆ
CER NO :...2918..... Dt: 12/03/19

TA to CE (YNK)
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ